

Quote UFEQ27451

Valid through January 30, 2020

Prepared For:

Tubac Fire Department # 1
Genaro Rivera
Phone: (520)761-1065
2227 E. Frontage Rd.
Tubac, AZ 85646
grivera@tubacfire.org

Prepared By:

Jeff Gilbert
Sr. Equip. Specialist
Phone: 520-306-1913
Fax: 800-882-3991
Email: jeffg@ufec.com



Jeff Gilbert






Below is the interactive version of the quote, you can choose options and see the quote totals.

For the full presentation proposal, [click here](#) to view or download the PDF version of this quote. You can sign and fax this in, or you can save time by simply electronically accepting this quote below.



Line Item Detail

QTY	Description	Picture	Unit Price	Ext Price
Bauer Verticus 10 hp - Breathing Air Compressor -				
1	Verticus 13 Breathing Air Compressor * 13 scfm, 4 STG, 6,000 psig service * 10 hp 208 volt/3-phase * 7" color HMI touchscreen display * NEMA 4 rated electrical enclosure * Compressor low oil pressure and high temperature safety shutdowns * Emergency stop push button and automatic start/stop control * Automatic drain system * P2 SECURUS Grade E purification, 67,000 cu ft * Interstage pressure gauges		\$29,836.28	\$29,836.28
1	Fill Station, 2 Position Two position CFS equipped with inlet pressure gauge adjustable regulator, regulated pressure gauge, fill control valve and fill pressure gauges. Dual function, top mount, four bank cascade panel. The dual function feature offers the ability to refill a storage bank, even with the bank valve closed, while filling SCBA's from another bank. It also includes an air direction valve allowing the operator to select fill from storage or fill from compressor Remote fill hose connection including bulkhead fitting, adjustable regulator for up to 6000 psig service, gauge, isolation valve, and quick connect/disconnect		\$12,390.94	\$12,390.94
5	Elbow,90 Deg,1/4 NPTM X 1/4 JIC		\$4.24	\$21.20
Installation & Training				
1	Compressor Installation & Training Set up and First start of the Compressor Hook up and install lines from compressor to the fill station Hook up to the existing cascade system. Training of personnel as designated by the Chief. To be trained on the day of the start up.		\$850.00	\$850.00
1	Shop Supplies Misc. fittings to connect fill station compressor,etc		\$75.00	\$75.00

NOTES

[NOTE A:] Customer Responsibilities:

- 1) Removal of the compressor from freight delivery vehicle
- 2) Placement of Equipment (The unit does not need to be bolted or permanently mounted to the floor)
- 3) Proper Electrical hook up, (by certified electrician), to compressor before start up. It is preferred to have the final connection to the compressor coordinated at the time the compressor is placed into service by the Bauer technician.
- 4) The unit must NOT be started prior to the installation process. Prior start-up not performed by a certified Bauer technician & inspection will result in voiding the warranty.

[NOTE B:] Electric Requirements / Specs

Voltages and Frequencies requirements must be specified at the time an order is placed. If you have specific requirements they must be confirmed with Bauer prior to the order being placed.

The unit(s) being proposed is:
"E3" = Three phase electric, 208 VAC/60 Hz

Freight - Shipping/Handling > 6-8 weeks

Freight is ESTIMATED - Firm pricing will be provided once selection is made on items. If Hydraulic Lift Gate is required additional charges will apply.

Please note on PO any special requests.

SubTotal:	\$43,173.42
Shipping:	\$3,000.00
Sales Tax:	\$3,682.14
Total:	\$49,855.56

Payment Options

<input type="radio"/> Purchase (Terms) Terms	\$49,855.56 full payment
<input type="radio"/> Purchase (Credit Card) Credit Card	\$49,855.56 full payment

Ready to Accept?

Order Confirmation

We reserve the right to cancel orders arising from errors, inaccuracies, or omissions.

I agree to the terms and conditions of the above document and PDF attachment with an electronic signature below.

IP Address 67.212.206.22

PO Number
(Optional: Enter PO Number as your reference only.)

Comments

Email Address

Printed Name

Signature

Have Questions?